

BANGALORE DIVISION.

ADVERTISEMENT.

The 6th August 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 21st August 1888, for constructing Silhadar Huts at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th March 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:

4. Each tender must be accompanied by a deposit of Rs. 50 only in cash or Government promissory notes as earnest money and be superscribed "Tender for constructing Silhadar Huts at Bangalore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Bill of quantities for constructing Silhadar Huts at Bangalore.

Items of Work.	Per.	Quantity.	Rate.	Cost.
Earthwork excavation	C. Yds.	27		
Stone in clay foundation and Casement	C. Ft.	844		
Burnt brick in clay	do	1,705		
Plastering with mud	Sqr.	12.15		
Pointing with chunam	do	10.06		
Honne wood work	C. Ft.	17.38		
Stone slabs	S. Ft.	103		
Color washing	Sqr.	13.80		
White washing	do	12.85		
Drains	R. Ft.	14		
Earthwork	C. Yd.	19		
Gravelling	do	19		
Roofing with 2nd class Mangalore tiles with honne wood-reepers	Sqr.	6.20		
Honne wood door 3' x 6'	No.	2		
Do 2½' x 5'	do	2		

R. T. SCALDWELL,
Executive Engineer.

SHIMOGA DIVISION.

ADVERTISEMENT.

The 1st August 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 20th August 1888, for opening out a Deviation road at Malebennur Ghat on Shimoga-Harihar road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A. M. to 5 P. M.